

SCOPE OF WORK

Brief Scope of works

The Contract Scope of work shall include but not limited to preparation of House Connection design sheets and shop drawing with all required details such as Data Collection, Latest MOH Maps, Chamber/Manhole Cover levels from Municipalities, Utilities (authorities) As-built information and data, Trial Pits, Collection of house connection information and data, etc. and Construction, Installation, Testing, Commissioning and all required to complete the works in accordance to OWWSC related Design Manuals, Standard Details, Specifications and Requirements for the following:

- Gravity pipes for internal diameters 75 mm to 200 mm
- Manholes
- Property Chambers
- House connection Chambers
- Reinstatement (all kinds)

The Contractor shall consider the following:

- All quantities are approximate and to obtain the Unit Rates and the Contractor will be paid as per the actual executed works.
- The drawings provided in the Tender document are only for information and the Contractor is responsible to prepare the House Connection Design sheets and Shop drawings to complete the network from the Existing system.
- There are Four types of connection.
- Break the pipe: Locate existing property/house/final chamber which was executed above the pipe towards septic tank. Chamber was executed during earlier stage of the Project. Temporary divert and maintain flow by any means necessary, clean chamber, break the existing line, block the line towards the septic tanks and any other works required for permanent diversion of the flow to OWWSC system-all in accordance to OWWSC Design Manuals, Standard details, Specifications and Requirements.
- House connection for plot develop in between earlier Project and today
- Demolition/Abandonment of existing septic tanks or soak away:
- Modification of existing property/house/final chamber

Time for Completion of the Works:

365 Days from the letter of acceptance for each Contract awarded to the contractor which is inclusive the mobilization period (15) calendar days in each .