



T/2459831/2023

CONSTRUCTION OF SEWER NETOWRK FOR C3B AREA IN A'SEEB CATCHMENT

BRIEF SCOPE OF WORK

- Scope of work for Contract <u>C3B</u> shall include but not limited to the construction (Supply, Installation & Commissioning) of the following:
 - Gravity sewer network/s ranging inner diameter from 200 mm to 600 mm
 - Gravity sewer manholes (lateral plus trunk)
 - House connection and rider sewers ranging diameter from 100mm to 185 mm
 - Property chambers, House connection chambers, Gravity sewer manholes (for Rider Lines)
 - The contractor shall design and construct the house connections for all plots located in project area.
 - Single Rising Mains with different diameter
 - C3B Pumping Stations (PS2 & PS4 & PS6)

The work shall include the following (but not limited to):

- Procurement and Construction of pump station, building complete with all civil, electrical, mechanical, plumping, firefighting, HVAC, Instrumentation & control and ICA works.
- Supply and installation of flow meter chamber, inlet valve chamber complete with all associated works.
- Provision for power supply from MEDC source till transformer building
- Construction of roads, fence works.
- Construction of Roads Crossing (open cut & Trenchless method) and complete with all necessary works.