



T/2542960/2023

Consultancy Service Supervision for Construction of Remaining Works of Sohar Sewage Network Phase -III

SCOPE FOR WORK:

To provide Consultancy Supervision for construction of remaining works of Sohar Sewerage Network Phase III. The

scope of work of the remaining works are not limited to the following;

- Construction of about 40 Km of conventional sewers with pipe diameters ranging from 150 mm to 1000 mm.
- Construction of vacuum sewage collection network for coastal areas with 500 m gravity sewer of 150mm and 2500m vacuum network of 90mm to 250mm.
- Construction of Ghail a'Shibool new proposed Lifting Station.
- Construction of about 3 Km of pumping mains with pipe diameters ranging from 150mm to 400 mm.
- Salance works of new Pump Stations at Hambar 1 and Tarayf.
- Upgrading of existing Pump Stations at Hijra, Hambar 6, C1.
- Salance works of Vacuum Stations at Hadirah and Shizaw.
- Balance works of Store and Workshop buildings.
- Construction of all other related works to make the project complete.
- Testing, commissioning of completed works.